GUIDE SPECIFICATION FOR HMA Ultra-Thin

1 of 4

- a. **Description.** This guide specification provides acceptance testing requirements for use on HMA Ultra-Thin Overlay mixture.
- b. Materials. The HMA and materials shall meet the following requirements:

1. Bond Coat. The bond coat material will be emulsified asphalt conforming to the requirements of Section 904 of the Michigan Department of Transportation (MDOT) Standard Specifications for Construction.

2. HMA Ultra-Thin Overlay. The Ultra Thin HMA Overlay shall be composed of a mixture of aggregate, asphalt binder, and if required, mineral filler, as listed in Table 1.

Parameter	
Air Voids %	4.5
VMA % (min.) based on Gsb	15.5
Fines/Binder % Max.	1.4
Nd	35

Table 1 - HMA Ultra-Thin Overlay Mixture Requirements

3. Aggregate Gradation and Physical Properties. The combined gradation of the aggregate portion of the mixture, including the mineral filler, shall be within the limits of Table 2. The physical properties of the combined aggregates shall meet the criteria of Table 3.

Total Passing Percent by Weight		
100		
99-100		
75-95		
55-75		
25-45		
3-8		

Table 2 - HMA Ultra-Thin Overlay Aggregate Gradation

Table 5 - InviA Ottra-Tinn Overlay Aggregate Thysical Requirements				
	Low Volume	Medium Volume	High Volume	
	Comm. ADT	Comm. ADT	Comm. ADT	
Parameter	<380	380 - 3400	>3400	
Percent Crush (min.)	50%	75%	95%	
Fine Aggregate Angularity Minimum Criteria	40	43	45	
L.A abrasion loss (max.)	40	35	35	
Aggregate Wear Index (AWI)	(a)	(a)	(a)	
a. AWI of 220 is required for projects with less than or equal to 2000 ADT, projects with				
ADT greater than 2000 the minimum AWI requirement is 260.				

Table 3 - HMA Ultra-Thin Overlay Aggregate Physical Requirements

In addition, the sum of the shale, siltstone, ochre, coal, clay-ironstone and particles which are structurally weak or are found to be non-durable in service shall not exceed 8.0 percent.

4. Performance Graded (PG) Asphalt Binder. Binder selection is based on present day two-way commercial ADT as listed in Table 4. The PG binder shall meet all the requirements in Section 904 of the MDOT Standard Specifications for Construction. Substitution of reclaimed asphalt pavement (RAP) for part of the new materials required to produce the HMA is acceptable as follows: Reclaimed Asphalt Pavement up to 27 percent binder by weight of the total binder in the mixture is allowed with no change in binder grade. For reclaimed asphalt pavement > 27 percent RAP binder by weight of the total binder in the mixture, the binder grade for the asphalt binder is selected using a blending chart for high and low temperatures. Supply the blending chart and the RAP test data used in determining the binder selection according to AASHTO M 323.

Table 4 - Asphalt Diffuel Selection for HistA Offia-Thin Overlay				
Low Volume	Medium Volume	High Volume		
Comm. ADT <380	Comm. ADT 380-3400	Comm. ADT >3400		
PG 58-28	PG 64 -28P	PG 70-28P		

Table 4 - Asphalt Binder Selection for HMA Ultra-Thin Overlay

c. Construction.

- 1. Bond Coat Application. The bond coat material will be applied to completely cover the prepared surface at a rate of 0.11 0.15 gal/yd2.
- 2. Mixture Application Rate. The target application rate shall be 83 lb/yd2, unless specified by the engineer to address special circumstances.
- 3. Mix Design. The Contractor shall submit to the Owner a complete mix design for review prior to the start of production.
- 4. Quality Control. The Contractor shall provide and follow a Quality Control (QC) plan for the Ultra Thin HMA Overlay that will maintain adequate QC for production and construction processes applicable to this specification and the contract documents. For QC purposes, the Contractor must perform at least one QC test per day for gradation, AC content, and air voids, and is allowed to take informational cores for application rates. The Owner shall be provided a copy of the QC plan for review, prior to mix production and placement.

After the job-mix-formula is established, the aggregate gradation and the binder content of the HMA mixture furnished for the work shall be maintained within the Range 1 uniformity tolerance limits permitted for the job-mix-formula specified in Table 5. However, if deviations are predominantly either below or above the job-mix-formula, the Owner may order alterations in the

plant to bring the mixture to the job-mix-formula. If two consecutive aggregate gradations on one sieve, or binder contents as determined by the QC tests, are outside Range1 but within Range 2 tolerance limits, the Contractor shall suspend all operations. Contract time will continue during these times when the plant is down. Before resuming any production, the Contractor shall propose, for the Owner's approval, all necessary alterations to the materials or plant so that the job-mix-formula can be maintained. The Owner, after evaluating for effects on AWI and mix design properties, will approve or disapprove such alterations.

PARAMETER	* Range 1	Range 2	
Air Voids**	± 1.0	± 2.0	
Binder Content	± 0.40	± 0.50	
% Passing # 8 and Larger Sieves	± 5.0	± 8.0	
% Passing # 30 Sieve	± 4.0	± 6.0	
% Passing # 200 Sieve	± 1.0	± 2.0	
* This range allows for normal mixture and testing variations. The mixture shall be			
proportioned to test as closely as possible to the Job-Mix-Formula.			
** Air Void limits apply to QC testing and are optional for Acceptance testing.			

Table 5 – Uniformity Tolerance Limits (for QC and Acceptance)

- 5. Crushed Particle Content. The crushed particle content of the aggregate used in the HMA mixture shall not be more than 10 percentage points above or below the crushed particle content used in the job-mix-formula nor less than the minimum specified for the aggregate in the project documents.
- 6. Density. Thoroughly compact the mixture immediately after placement using the number of rollers method.
 - i. **Number of Rollers Method.** The number of compactive and finish rollers used shall be as specified in Table 6 based on the square yards per hour of Ultra Thin HMA Overlay being placed.

Average Laydown	Number of Rollers Required		
Rate, square	Compaction	Finish	
yards per hour	Rollers	Rollers	
Less than 800	1	1*	
801 - 2000	1	1	
2001 - 5500	2	1	
5501 - 7200	3	1	

 Table 6 – Number of Rollers Required based on Placement Rate

*The compaction roller may be used as the finish roller also.

d. Acceptance Sampling and Testing. Acceptance sampling and testing may be performed by the Owner. Each day of production, a minimum of two samples will be obtained for each mix type. Acceptance testing will be performed at the frequency specified by the Owner. No less than three samples shall be obtained for each mix type.

e. **Rejected Mixtures.** If for any one mixture, two consecutive aggregate gradations on one sieve or binder contents as determined by acceptance tests exceed the uniformity tolerance of Range 2 under Table 5, or do not meet the minimum requirements for crushed particle content specified in the project documents, the mixture will be rejected. If such mixtures are placed in a pavement, the remaining portions of the failing acceptance samples (split sample) will be sent to an independent Laboratory to confirm the acceptance test results. If the Laboratory's results do not confirm the acceptance test results, then no price adjustments will be made for the mixture involved. If the Laboratory's results confirm the acceptance test results and if, in the Owner's judgment, the defective mixture can remain in place, the contract unit price for the defective mixture

involved, as determined from acceptance tests, will be decreased on the following basis: The contract unit price for material outside of Range 2 will be decreased 25 percent.

The Owner may take into account the Contractor's QC test results when making acceptance decisions and price adjustments.

f. **Measurement and Payment.** The completed work as measured will be paid for at the contract unit price for the following contract item:

Contact Item (Pay Item) HMA, Ultra-Thin, Low Volume, HMA, Ultra-Thin, Medium Volume, HMA, Ultra-Thin, High Volume, HMA, Ultra-Thin Mix, Special Pay Unit Square Yard or Ton Square Yard or Ton Square Yard or Ton Ton

Payment for HMA, Ultra-Thin, Low, Medium and High Volume, includes all materials, equipment, labor for preparing the surface, placing temporary pavement markings, placing the HMA Ultra-Thin Overlay mixture and complying with all requirements. The placement includes placement of a single course of mixture for full width coverage as specified in the plans.

Payment for HMA, Ultra-Thin Mix, Special, includes all materials, equipment, labor for preparing the surface, placing the HMA Ultra-Thin Overlay mixture for special situations (wedging, scratch course, etc.) and complying with all requirements.

This document was developed by the Asphalt Pavement Association of Michigan (APAM). It is intended to be used as a resource in the design and construction of HMA Ultra-Thin in Michigan. APAM can not accept any responsibility for the inappropriate use of these documents. Engineering judgment and experience must be used to properly utilize the principles and guidelines contained in this document, taking into account available equipment, local materials and conditions. All reasonable care has been taken in the preparation of this guideline; However, the Asphalt Pavement Association of Michigan can not accept any responsibility for the consequences of any inaccuracies which it may contain.